



CLIENT: Grand View Distribution Corp

2386 Oak Street, Vancouver British Columbia, Canada, V6H 4J1

Test Report No: RJ5272P-1 Date: March 13, 2017

**SUBJECT:** Bond Strength Testing on: Alucolam Metal Composite Material.

**SAMPLE ID:** 6 mm thick injection molded metal composite material (MCM) core panels.

SAMPLING DETAIL: Test samples were submitted to the laboratory directly by the client. No special

sampling conditions or sample preparation were observed by QAI.

**DATE OF RECEIPT:** Samples were received at QAI Laboratories on February 8, 2017.

**TESTING PERIOD:** February 27, 2017.

**AUTHORIZATION:** QAI Test Proposal 17MM01232 signed by Cherie Ho on January 24, 2017.

TESTS REQUESTED: Bond Strength Test per ASTM C 297/C 297M-04, Standard Test Method for Flatwise

Tensile Strength of Sandwich Constructions.

**TEST RESULTS:** Test results are provided on subsequent pages of this report.

**Prepared By** 

David Royer
Physical Testing

Signed for and on behalf of QAI/Daboratories Inc.

Drew Mersereau Project Manager

Page 1 of 4

THIS REPORT IS THE CONFIDENTIAL PROPERTY OF THE CLIENT ADDRESSED. THE REPORT MAY ONLY BE REPRODUCED IN FULL. PUBLICATION OF EXTRACTS FROM THIS REPORT IS NOT PERMITTED WITHOUT WRITTEN APPROVAL FROM QAI. ANY LIABILITY ATTACHED THERETO IS LIMITED TO THE FEE CHARGED FOR THE INDIVIDUAL PROJECT FILE REFERENCED.

THE RESULTS OF THIS REPORT PERTAIN ONLY TO THE SPECIFIC SAMPLE(S) EVALUATED.



Client: Grand View Distribution Corp Test Report No: RJ5272P-1

> Date: March 13, 2017 Page 2 of 4

Page 2 01 4

### BOND STRENGTH TEST PER ASTM C 297/ C 297M-04

#### **Test Procedure**

Testing was performed in accordance with ASTM C 297/C 297M-04, Standard Test Method for Flatwise Tensile Strength of Sandwich Constructions. The sample was conditioned to  $70 \pm 3^{\circ}F$  and  $50 \pm 4\%$  relative humidity for not less than 72 hours prior to testing. After conditioning, 2" square specimens were cut from the submitted sample and bonded to aluminum test blocks. The specimens were then individually placed in a United Tension/Compression Machine and pulled in tension at a constant rate of 0.02 inches per minute to failure.

### **Test Results**

Sandwich Construction Bond Strength Test				
Specimen	Area (in²)	Max Load (lbs)	Tensile Strength (psi)	Failure Mode
1	4.02	2986	743	Internal Panel-Cohesive
2	4.02	2783	692	Internal Panel-Cohesive
3	4.00	2648	661	Internal Panel-Cohesive
4	4.01	2607	650	Internal Panel-Cohesive
5	4.03	2833	703	Internal Panel-Cohesive
Average	4.02	2771	690	




Client: Grand View Distribution Corp Test Report No: RJ5272P-1

Date: March 13, 2017

Page 3 of 4

# **Photograph**



Photograph No 1: Test Setup




Client: Grand View Distribution Corp Test Report No: RJ5272P-1

Date: March 13, 2017

Page 4 of 4

# **Photograph**



Photograph No 2: Typical Mode of Failure: Cohesive Failure Within the Specimen

\*\*\*\*<<<End of Report>>>\*\*\*\*

THIS REPORT IS THE CONFIDENTIAL PROPERTY OF THE CLIENT ADDRESSED. THE REPORT MAY ONLY BE REPRODUCED IN FULL. PUBLICATION OF EXTRACTS FROM THIS REPORT IS NOT PERMITTED WITHOUT WRITTEN APPROVAL FROM QAI. ANY LIABILITY ATTACHED THERETO IS LIMITED TO THE FEE CHARGED FOR THE INDIVIDUAL PROJECT FILE REFERENCED.

THE RESULTS OF THIS REPORT PERTAIN ONLY TO THE SPECIFIC SAMPLE(S) EVALUATED.