

## Section 07 42 00 – Composite Metal Panels

### Part 1 General

#### 1.1 SUMMARY

- .1 Work of this section includes provision of the following:
  - .1 Aluminum Composite Material (ACM) Panel System.
  - .2 Fastening system.
  - .3 Sub-girt system.
  - .4 Engineering by Sub-Contractor.

#### 1.2 RELATED REQUIREMENTS

- .1 Section 05 41 00 - Structural Metal Stud Framing
- .2 Section 06 16 43 - Gypsum Sheathing
- .3 Section 07 05 42 - Thermally Improved Cladding Support Systems
- .4 Section 07 14 16 - Cold Fluid-Applied Waterproofing
- .5 Section 07 21 13 - Board Insulation
- .6 Section 07 27 13 - Modified Bituminous Air and Vapour Barrier
- .7 Section 07 62 00 - Sheet Metal Flashing and Trim
- .8 Section 07 92 00 – Sealants

#### 1.3 REFERENCES

- .1 Aluminum Association, Inc. (AA)
  - .1 AA 3003 - Non-Heat Treatable Aluminum Manganese Copper Alloy; 2009.
  - .2 AA 5005 - Non-Heat Treatable Aluminum Magnesium Alloy; 2010
  - .3 AA 6061 - Heat Treatable Aluminum Silicon Alloy; 2009
  - .4 AA 6063 - Heat Treatable Aluminum Magnesium Silicon Alloy; 2009.
- .2 American Aluminum ACM Manufacturers Association (AAMA)
  - .1 AAMA 508 - Voluntary Test Method and Specification for Pressure Equalized Rain Screen Wall Cladding Systems; 2014.
  - .2 AAMA 620 - Voluntary Specification for High Performance Organic Coatings on Coil Coated Architectural Aluminum Substrates; 2002.
  - .3 AAMA 2605 - Voluntary Specification, Performance Requirements and Test Procedures for Superior Performing Organic Coatings on Aluminum Extrusions and Panels (with Coil Coating Appendix); 2017a.

- .3 American Society for Testing and Materials International (ASTM)
  - .1 ASTM C297/C297M – Standard Test Method for Tensile Strength for Flatwise Tensile Strength of Sandwich Constructions; 2010
  - .2 ASTM C-365 - Standard Test Method for Flatwise Compressive Properties of Sandwich Cores; 2005
  - .3 ASTM D-790 Standard Test Methods for Flexural Properties of Unreinforced and Reinforced Plastics and Electrical Insulating Materials; 2010
  - .4 ASTM D-638 Standard Test Method for Tensile Strength of Plastics; 2014.
  - .5 ASTM C-518 Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus; 2010
  - .6 ASTM C-272 Standard Test Method for Water Absorption of Core Materials for Sandwich Construction; 2012
  - .7 ASTM C-273 Standard Test Method for Shear Properties of Sandwich Core Materials; 2011
  - .8 ASTM D-696 Standard Test Method for Coefficient of Linear Thermal Expansion of Plastics Between –30°C and 30°C with a Vitreous Silica Dilatometer; 2008
  - .9 ASTM D1781 - Standard Test Method for Climbing Drum Peel for Adhesives; 2012
  - .10 ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2018
  - .11 ASTM E-90 – Standard Test Method Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements; 2009
  - .12 ICC-ES ESR-4261 – Compliance with the following codes 2018, 2015, and 2012 *International Building Code (IBC)* For evaluation for compliance with codes adopted by Los Angeles Department of Building and Safety (LADBS), see ESR-4261 LABC Supplement.  
For evaluation for compliance with codes adopted by the California Office of Statewide Health Planning and Development (OSHPD) and Division of the State Architect (DSA), see ESR-4261 CBC Supplement.
  - .13 ICC-ES LABC Supplement – Compliance with the codes noted below as adopted by the Los Angeles Department of Building and Safety (LADBS). 2020 *City of Los Angeles Building Code (LABC)*
  - .14 ICC-ES ESR 4261 CBC Supplement – Compliance with code(s) noted below  
*2019 California Building Code (CBC)*  
For evaluation of applicable chapters adopted by the California Office of Statewide Health Planning and Development (OSHPD) and Division of State Architect (DSA)

#### 1.4 ADMINISTRATIVE REQUIREMENTS

- 
- .1 Convene pre-installation meeting prior to beginning work of this Section and on-site installation, with Contractor, Consultant, Panel Fabricator, Panel Installer, and ACM Manufacturer to:
    - .1 Verify project requirements.
    - .2 Review installation and substrate conditions.
    - .3 Co-ordination with other building sub-trades.
    - .4 Review installation method and warranty requirements.
    - .5 Review field quality control procedures.
  - .2 Panel Fabricator's representative shall also provide frequent inspection visits during the course of work of this Section to assure quality and competence of panel installation.

### 1.5 SUBMITTALS

- .1 Provide submittals in accordance with Division 01 Requirements and procedures
- .2 LEED Submittals: in accordance with requirements of Division 01 Requirements – LEED Requirements; submit product information and supporting documentation for verification related to following Credits:
  - .1 MR Credit 4 Recycled Content.
- .3 Product Data
  - .1 Submit ACM Manufacturer's printed product literature, specifications and datasheet.
- .4 Shop drawings
  - .1 Submit shop drawings indicating attachment methods, joinery, sealing methods and accommodation of thermal movement. Details shall not be drawn less than full size.
- .5 Samples
  - .1 Submit duplicates of ACM Manufacturer's standard sized samples of composite panel in specified thickness, finishes, and selected colours. Allow for review at panel fabrication facility of clips, anchors, supports, fasteners, closures, and other panel accessories for assembly approval.
  - .2 Samples for Verification: Provide two (2) – 12"x12" samples of selected color prior to ordering material, in the profile, style, color and texture indicated. Include clips, caps, battens, fasteners, closures and other exposed panel accessories.
  - .3 Qualification Data: for firms and persons specified in the "Quality Assurance" Article to demonstrate their capabilities and experience. Include lists of completed projects with project names and addresses, names and addresses of Consultants and owners, and other information specified.
  - .4 Product Test Reports: Indicate compliance of manufactured wall panel assemblies and materials with performance and other requirements based on comprehensive testing of current products.
- .6 ACM Manufacturer & Panel Fabricator's Instructions

- 
- .1 Submit installation instructions
  - .2 Submit special handling criteria and cleaning procedures.
  - .3 Aluminum wall panels and components shall comply with details as indicated on drawings and as indicated in shop drawings.
  - .4 All components shall be factory fabricated ready for field installation. All components shall match quality and installation of accepted mock-up specified below.

- .7 Quality assurance submittals
  - .1 Test Reports: certified test reports showing compliance with specified performance characteristics and physical properties.
  - .2 Certificates: submit certificates signed by ACM Manufacturer certifying that composite wall panels comply with specified performance characteristics and physical properties.

## 1.6 QUALITY ASSURANCE

- .1 ACM Manufacturer
  - .1 Company specializing in manufacturing composite panel products specified by this Section.
- .2 Panel Fabricator
  - .1 Company specializing in designing, engineering, and fabricating wall panels of this Section.
  - .2 Aluminum wall panels and components shall comply with details as indicated on drawings and as indicated in shop drawings.
  - .3 All components shall be factory fabricated ready for field installation. All components shall match quality and installation of accepted mock up specified below
  - .4 Approved Panel Fabricator
    - .1 SERIES 35 aluminum composite panels.[www.grandvieweas.com](http://www.grandvieweas.com)
- .3 Panel Installer
  - .1 Company specializing in installing work of this Section.
  - .2 Installer Qualifications: engage an experienced installer who has completed metal wall panel projects similar in design, and extent to that indicated for this project and with a record of successful performance.
  - .3 Painted surfaces of composite panels shall meet criteria printed in the manufacturer's literature.
  - .4 Confirm field measurements prior to completion of shop fabrication.

### **1.7 MOCK-UPS**

- .1 Construct mock-ups if necessary in accordance with Division 01 Requirements
- .2 Cost of mock-up(s) are separate from Sub-trade Contract Price and are to be submitted to Contractor for review and approval by Owner
- .3 Construct mock-ups in locations as directed by Consultant:
  - .1 Provide mock-up for evaluation of surface finishes and workmanship.
  - .2 Construct mock-up indicating relationship between wall panels, air spaces, air/vapour retarder membrane, windows, and doors.
  - .3 Remove and replace units which are not accepted.
  - .4 Do not proceed with remaining work until workmanship, colour, and finish are reviewed by Consultant.
  - .5 Refinish mock-up area as required to produce acceptable work.
  - .6 When accepted, mock-up will demonstrate minimum standard of quality required for this work.
    - .1 Approved mock-up may remain as part of finished work.

### **1.8 DELIVERY, STORAGE AND HANDLING**

- .1 Deliver components, aluminum composite material panels, and other manufactured items so as not to be damaged or deformed. Package aluminum composite material panels for protection during transportation and handling.
- .2 Handling: Exercise care, Unload, store, and erect aluminum composite material panels in a manner to prevent bending, warping, twisting, and surface damage.
- .3 Stack aluminum composite material panels horizontally on platforms or pallets, covered with suitable weathertight and ventilated covering. Store aluminum composite material panels to ensure dryness, with positive slope for drainage of water. Do not store aluminum composite material panels in contact with other materials that might cause staining, denting, or other surface damage.
- .4 Retain strippable protective covering on aluminum composite material panels during installation.

### **1.9 WASTE MANAGEMENT AND DISPOSAL**

- .1 Separate waste materials for recycling and disposal in accordance with Division 01 Requirements.

### **1.10 WARRANTY**

- .1 Workmanship Warranty
  - .1 Installer agrees to repair or replace components of the panel system that fail in workmanship within specified warranty period. Failures include all items in relation to the following:
    - .1 Structural failures.
    - .2 Rainscreen performance failures.
  - .2 Warranty Period: Two years from date of Substantial Completion.

- .2 Aluminum Composite Material (ACM) Warranty
  - .1 ACM Manufacturer's standard warranty in which Manufacturer agrees to repair finish or replace aluminum composite material panels that show evidence of deterioration. Deterioration of finish includes, but is not limited to, colour fade, chalking, cracking, peeling of factory-applied finishes within specified warranty period under the following criteria:
    - .1 Color fading more than 5 Hunter units when tested according to ASTM D 2244.
    - .2 Chalking in excess of a No.8 rating when tested according to ASTM D 4214.
    - .3 Cracking, checking, peeling, or failure of paint to adhere to bare metal.
  - .2 Finish Warranty Period: 20 years from date of Substantial Completion.

## **PART 2 PRODUCTS**

### **2.1 SYSTEM DESCRIPTION**

- .1 Factory-formed and assembled, site installed, aluminum composite material wall panels fabricated from two metal facings bonded to a solid non-combustible core; formed into profile for installation method indicated.
- .2 Attachment components including perimeter frame, tracks and clips to be extruded aluminum
- .3 Panel perimeter frame shall consist of factory-installed hidden panel perimeter gasket that reduces moisture entry into the Rainscreen cavity and minimizes noise from movement.
- .4 System shall be of pressure-equalized Rainscreen design as tested per AAMA 508. Lag time between the cavity and cyclic wind pressure (5 PSF to 25 PSF) shall not exceed 0.08 seconds. The maximum differential between the cavity pressure and the external wind pressure shall not exceed 8%
- .5 Wall panel system shall be designed for positive drainage of water leakage and condensation to exterior of wall panel system, including gutter system and hidden flashing at each horizontal joint.

### **2.2 PERFORMANCE/DESIGN REQUIREMENTS**

- .1 Structural Performance: Provide aluminum composite material panel systems capable of withstanding the effects of the following loads, based on testing according to ASTM E 330:
  - .1 Wind Loads: As indicated on Drawings.
  - .2 Other Design Loads: As indicated on Drawings.
  - .3 Deflection Limits: For wind loads, refer to Appendix 1.
- .2 Seismic Performance
  - .1 Aluminum composite material wall panels shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.

- .3 Air Infiltration
  - .1 When tested according to ASTM E 283, air leakage of not more than 0.02 cfm/sq. ft. (0.1 L/s per sq. m) at a test-pressure difference of 6.24 lbs/sq. ft. (300 Pa).
- .4 Water Penetration under Static Pressure
  - .1 When tested according to ASTM E 331, no water penetration under static pressure differential of 20% of inward acting design load at a test-pressure difference of 12 lbs/sq. ft. (600 Pa).
- .5 Water Penetration under Dynamic Pressure
  - .1 Tested according to AAMA 501.1:
    - .1 No evidence of water penetration through fixed glazing and framing areas when tested at dynamic pressure equal to 20 percent of positive wind-load design pressure, but not less than 12 lbs/sq. ft. (600 Pa).
    - .2 Water leakage does not include water controlled by flashing and gutters, or water that is drained to exterior.
- .6 Pressure Equalized Rainscreen
  - .1 Tested to AAMA 508-07
    - .1 The panel Fabricator must provide an official test report from an independent testing agency that graphs the performance of the panel system when subject to the AAMA 508-07 test criteria
    - .2 Lag time between the cavity and cyclic wind pressure (5 PSF to 25 PSF) shall not exceed 0.08 seconds. The maximum differential between the cavity pressure and the external wind pressure shall not exceed 8%. For example, at 25 PSF External Wind Pressure, the cavity pressure should not fall below 23 PSF.
- .7 Thermal Movements
  - .1 Allow for thermal movements from ambient and surface temperature changes by preventing buckling, opening of joints, overstressing of components, failure of joint sealants, failure of connections, and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.
    - .1 Temperature Change (Range): 120 deg F (67 deg C), ambient; 180 deg F (100 deg C), material surfaces.
- .8 Fire Performance
  - .1 For Combustible Construction permitted
    - .1 Tested to ASTM E 84
    - .2 Max. Flame Spread 25, Max. Smoke Developed 450

## 2.3 COMPOSITE METAL PANEL SYSTEM MATERIALS

- 
- .1 Aluminum Composite Material (ACM): aluminum sheets thermally bonded in continuous process, under tension, to fire rated core with no glues or adhesives between dissimilar materials, and as follows:
    - .1 Basis of Design
      - .1 SERIES 35 manufactured by Grandview EAS
    - .2 4mm Total Composite Thickness
    - .3 Aluminum face sheets:
      - .1 Thickness: 0.50 mm.
      - .2 Alloy: AA 5005.
      - .3 Factory Finish: coil coated with fluoropolymer paint to AAMA 620 and AAMA 2605.
    - .4 Fire rated core in accordance to NFPA 285 in the United States
    - .5 Bond Integrity
      - .1 When tested, in accordance with ASTM D1781 (simulating resistance to panel delamination), there shall not be an adhesive failure of the bond between the core and the skin or a cohesive failure of the core itself according to the following values:
        - .1 Bond Strength: 1160 psi to ASTM C297/C297M.
        - .2 Peel Strength: 100 N mm/mm minimum to ASTM D1781.
        - .3 No degradation in bond performance after 8 hours of submersion in boiling water and after 21 days of immersion in water at 21 degrees C.
  - .2 Panel System:
    - .1 Basis of Design
      - .1 Series 35 Rainscreen panel system by Grandview EAS
    - .2 Attachment assembly components
      - .1 Perimeter frame, tracks and clips to be formed of aluminum extrusions
        - .1 Alloy T 6063 Mill Finish

## 2.4 SYSTEM BACK-UP MATERIALS

- .1 Fasteners: corrosion resistant
- .2 Thermally broken façade substructure (if required by jurisdiction):
  - .1 Attributes:
    - .1 Non-combustible
    - .2 Meet requirements of ASHRAE 90.1 for project location
    - .3 Adjustable to permit façade alignment to meet installation tolerances.
    - .4 Suitable for rear ventilated rain screen façade design.
- .3 Perimeter Extrusion Panel Clip
  - .1 Acceptable Product: Grandview Panel Clip extrusion For Series 35 Panel System.
- .4 Girts and sub-girts as detailed: custom manufactured z-girts, Galvalume steel to ASTM A792/A792M, 18 Ga. (1.2 mm) thickness, profiles as indicated, AZM 150 coating.



- 
- .5 Isolation Tape: ACM Manufacturers standard material for separating dissimilar metals from direct contact.

## 2.5 ACCESSORIES

- .1 System Sealants: Panel system to be dry-joint Rainscreen with no reliance on surface applied sealants.
- .2 Gaskets: Silicone perimeter gasket as recommended by Panel Fabricator.
- .3 Continuous J-track Aluminum Extrusion - continuous aluminum extrusion that engages pocket of panel perimeter extrusion for the purposes of fastening panel system to substrate, field applied.
- .4 Stiffener Extrusion – factory applied internally to panel for deflection purposes as required and specified by Engineer to meet code requirements.
- .5 Flashings : fabricate flashings from aluminum sheet. Where exposed to view, finish matching adjacent panels

## 2.6 FINISH

- .1 Prefinished sheet with factory applied coating to AAMA 2605, Polyvinylidene Fluoride (PVDF) or Fluoroethylene Vinyl Ether (FEVE).
  - .1 Colour: to be selected by Consultant from ACM Manufacturer's full colour range.
  - .2 Custom colour(s): [to be noted here; Consultant understands that custom colours may be associated with additional set-up fees]
  - .3 Finish as indicated on drawings.

## 2.7 FABRICATION

- .1 Panels and components shall comply with details as indicated on drawings and as indicated in reviewed shop drawings.
- .2 Panel system shall be shop fabricated
- .3 Components shall match quality and installation of accepted mock-up specified above.
- .4 Drill 4.7 mm (3/16 inch) drainage weep holes 2 per panel at ¼ points along length of horizontally oriented bottom end frames located at base of panelized wall areas.
- .5 Tolerances:
  - .1 Panel bow shall not exceed 0.8% of panel overall dimension in width or length.
  - .2 Panel dimensions shall allow for field adjustment and thermal movement.

- 
- .3 Panel lines, breaks and curves shall be sharp, smooth and free of warps or buckles.
  - .4 Panel shall be visually flat.
  - .5 Panel surfaces shall be free of scratches or marks caused during fabrication.

### **Part 3 Execution**

#### **3.1 ACM MANUFACTURER'S INSTRUCTIONS**

- .1 Compliance: comply with ACM Manufacturer's written recommendations or specifications, including product technical bulletins, handling, storage and installation instructions, and datasheets.

#### **3.2 PREPARATION**

- .1 Obtain dimensions from job site.
- .2 Ensure all structural support is aligned and condition is acceptable.
- .3 Building surfaces shall be smooth, clean and dry, and free from defects detrimental to the installation of the system. Notify Contractor of conditions not acceptable for installation of system.
- .4 Inspect wall system and components before installation and verify that there is no shipping damage.
- .5 Do not install damaged panels; repair or replace as required for smooth and consistent finished appearance.

#### **3.3 INSTALLATION**

- .1 Install composite panels in accordance with ACM Manufacturer's written instructions and shop drawings.
- .2 Ensure continuity of building envelope air barrier and vapour retarder systems.
- .3 Erect panels plumb, level and true.
- .4 Do not install component parts that are observed to be defective, including warped, bowed, dented, scraped and broken members.
- .5 Adjust assembly to secure panels safely to wall while allowing for expansion and contraction of components.
- .6 Do not cut, trim, weld, or braze component parts during erection in manner which would damage finish, decrease strength, or result in visual imperfection or failure in performance.

- .7 Return component parts which require alteration to shop for fabrication, if possible, or for replacement with new parts.
- .8 Ensure panels aligned vertically and horizontally.
- .9 Separate dissimilar metals; use appropriate gaskets and tapes to minimize corrosive or electrolytic action between metals.
- .10 Install flashings to divert all moisture and condensation to exterior. Trim and flash around doors, louvers, and windows. Use only membrane flashing supported by insulation per architectural details.
- .11 Site Tolerances:
  - .1 Variation from plane or location shown on shop drawings: 10 mm over 10 m (0.4 inches over 33-foot) length to maximum of 20 mm over 100 m (0.79 inches over 328 feet).
  - .2 Deviation of vertical and horizontal members: 3 mm maximum over 8.5 m (0.12 inches over 28-feet) run.
  - .3 Offset between two adjacent members abutted end-to-end, in line: maximum 0.75 mm (0.03 inch) from true alignment
- .12 Touch-Up Painting: Inspect completed wall system and apply matching touch-up paint as needed to correct minor paint flaws.

### **3.4 FIELD QUALITY CONTROL**

- .1 Panel Fabricator's Field Services:
  - .1 Panel Fabricator to provide field services consisting of product use recommendations and periodic site visits for inspection of product installation in accordance with Panel Fabricator's instructions.

### **3.5 CLEANING**

- .1 Clean in accordance with ACM Manufacturer's instructions.
- .2 Remove and replace panels damaged beyond repair as direct result of panel installation.
- .3 Repair panels with minor damage. Touch-up damaged finishes with manufacturer's recommended touch-up paint.
- .4 Remove protective film from finish panels immediately once installation is complete or as otherwise directed by Consultant.
- .5 Provide additional protection required after installation to protect assembly and finishes during construction.
- .6 Weep holes and drainage channels shall be unobstructed and free of dirt and sealants.

Project Name  
Project Location  
Project No. #

Section 07 42 00  
COMPOSITE METAL PANELS

---

- .7 Upon final acceptance of installation, remove surplus and protective materials, excess materials, rubbish, tools and equipment from site.
  
- .8 General Contractor to leave panels clean and free of debris and residue. Where required, clean exposed panel surfaces using non-abrasive detergent and clean water in accordance with ACM Manufacturer's instructions.

**End of Section**